

EVENT RISK ASSESSMENT

Event: Floe

Event Dates: 9th-11th December 2017 18.00-22.00

On-site Dates: 6th-12th December 2017

Site Address: The Deep, Hull

Risk Assessment date: 29th November 2017

Site visit by: Paul Wigfield

CONTENTS:

Page 2-3	Section 1: Introduction
Page 4	Section 2: Electrical
Page 5	Section 3: Projection Installation
Page 6	Section 4: Installations in Public Areas
Page 6	Section 5: Staff Manual Handling
Page 7	Section 6: Working at Height – Ladders
Page 8	Section 7: Slips and Trips
Page 9	Section 8: Fire Safety
Page 10	Section 9: Vehicle Movements
Page 10	Section 10: Further action required & additional notes



SECTION 1: INTRODUCTION

This is a site-specific risk assessment and method statement to supplement QED Productions Ltd's existing Health & Safety Policy.

QED Productions Ltd is supplying a D&B sound system to be positioned on the southern side of The Deep building.

This risk assessment identifies specific hazards and their risk ratings, control measures, and risk ratings after the control measures have been implemented.

QED Productions Ltd's management will ensure that staff are made aware of the significant findings of this risk assessment and the control measures necessary to eliminate or reduce the level or risk to the lowest possible level. A copy of this risk assessment should be available to all staff on site.

This Risk Assessment supplements any other risk assessments covering activities involving vehicle movements, structure construction and power generation.

Definitions

Hazard	The Hazard is something with the potential to cause harm, e.g. electricity, working at height, chemicals, vehicles
Risk	Combination of the likelihood and consequences of a specified hazardous event occurring.
Control Measures	The measures necessary to eliminate or reduce the level of risk
Risk Rating Without Controls	Level of risk before and control measures are implemented
Risk Rating With Controls	Level of risk after control measures have been implemented



SECTION 1: INTRODUCTION (Cont.)

Method used to determine the Risk Rating:

Likelihood (L)	The likelihood of harm occurring as a result of the hazard:
	1 = Very unlikely
	2 = Unlikely
	3 = Possible
	4 = Very likely
	5 = Certain
Potential Severity (S)	The potential severity of harm caused:
	1 = Injury, no time off work
	2 = Injury, time off work
	3 = More than three days off work
	4 = Long term absence
	5 = Death
Risk Rating (R)	Risk Rating = Likelihood (of the hazard occurring) X Potential Severity (of the loss):
	Low = 7 or less
	Med = 8 to 14
	High = 15 or greater



Hazard	Those at Risk	Risk Rating Without Controls			Control Measures	Risk Rating Wit		
		L	S	R	1	L	S	R
Electrocution (240V and 415V)	Staff, other workers on site, Public	3	5	High	 QED is hiring in a 50KVA generator from Elecplant to supply power for the external sound system All electrical equipment supplied by QED will have PAT certification Cables should be routed away from walkways and moveable items that could damage or break cables, e.g. furniture, etc. 	1	5	Low
Trips over cables	Staff, other workers on site, Public	4	4	Med	Staff will constantly monitor the site during the event	1	4	Low
Fire (electrical short circuits, overloads)	Staff, other workers on site, Public	2	5	Med	 All electrical circuits should be protected by fuses or MCBs and RCDs Staff will constantly monitor the site during the event 	1	5	Low



Hazard Those at	Those at Risk	Risk F Conti	_	Vithout	Control Measures	Risk Rating With Controls			
		L	S	R		L	S	R	
Electrocution (240V and 415V)	Staff, other workers on site, Public	3	5	High	See Section 2 - Electrical	1	5	Low	
Fire	Staff, other workers on site, Public	1	5	Low	Sound System to be installed with reference to manufacturer's guidelines	1	5	Low	
Working at height	Staff, other workers on site, Public	N/A	N/A	N/A	No working at height involved	N/A	N/A	N/A	
Manual handing of AV equipment	Staff, Public	4	3	Med	 all equipment to be handled in accordance with handling procedures as detailed in QED's manual handling policy Staff will have received manual handling training 	2	3	Low	



SECTION 4: INSTALLATIONS IN PUBLIC AREAS										
Hazard Those at Risk			Rati hout	ng Controls	Control Measures	Risk Rating With				
		L	S	R		L	S	R		
Personnel circulating in work areas	Staff, Public	4	2	Med	 If any unauthorised persons are in the work area, installation should stop until the work area is clear Team working wherever possible to maximise vigilance for above processes Hull 2017 to provide 24 hour security personnel 	1	2	Low		

SECTION 5: GENERAL STAFF MANUAL HANDLING											
Hazard Those at Risk	Those at Risk		Rati hout	ng Controls		Risk Rating Wi					
		L	S	R		L	S	R			
Manual handling (e.g. flight-cases, loudspeakers etc.)	Staff, Public	3	4	Med	 Equipment delivered as close as possible to area where used Team lifting as necessary Staff to be shown correct lifting techniques as appropriate Majority of equipment delivered in wheeled flight-cases 	1	4	Low			



SECTION 6: WORKING AT HEIGHT - LADDERS												
Hazard	Those at Risk		Rating out Cor	ntrols	Control Measures	Risk Rating With Controls						
		L	S	R		L	S	R				
Fall from Height	Staff, Public	N/A	N/A	N/A	QED is not intending to use ladders	N/A	N/A	N/A				
Objects falling from height	Staff, other workers on site, Public	N/A	N/A	N/A	No working at height involved	N/A	N/A	N/A				



		Risk Rating Without Controls				Risk Rating Wit		
Hazard	Those at Risk				Control Measures	Controls		
		L	S	R		L	S	R
Spilt liquids	Staff, other workers on site, Public	1	4	Low	 QED is not intending to use any liquids on site other than drinks Any spills to be cleaned up straight away Staff will constantly monitor the site during the event 	1	4	Low
Trips over cables	Staff, Other workers on site, Public	4	4	Med	 Cables to be routed away from traffic routes wherever practicable Any cables over traffic routes should be flown, covered with suitable matting or approved vehicle-rated ramps Staff will constantly monitor the site during the event 	1	3	Low
Trips over floor-standing equipment	Staff, other workers on site, Public	4	4		 Equipment to be sited away from traffic routes and within structures Equipment feet to be placed to minimise trip hazard Any equipment feet regarded as a potential trip hazard to be 	1	4	Low

clearly marked with hazard tape



SECTION 8: FIRE SAFETY										
Hazard Those at	Those at Risk	Risk Rating Without Controls			Control Measures	Risk Rating With Controls				
		L	S	R		L	S	R		
Fire (localised)	Staff, other workers on site, general public	2	5	Med	 Staff to monitor control areas and prevent the build up of any rubbish QED is not bringing any flammable liquids on to site All electrical circuits installed by QED to be protected by suitable RCDs 	1	4	Low		
Fire (building / structures)	Staff, other workers on site, general public	2	5	Med	 The event organisers are in control of fire safety for staff and public The organiser is in control of site fire safety A copy of the organiser's fire safety plan should be made available to staff on site 	1	3	Low		



SECTION 9: VEHICLE MOVEMENTS											
Hazard Th	Those at Risk	Risk Rating Without Controls			Control Measures	Risk Rating With Controls					
		L	S	R	L	L	S	R			
Collision with person, vehicle or object	Staff, other workers on site, general public	2	5	Med	 Vehicles only to operate as authorised by site staff Reversing with banksman if driver has restricted view Scheduling of vehicle movements for quiet times Comply with all venue vehicle regulations 	1	4	Low			

SECTION 10: FURTHER ACTION REQUIRED & ADDITIONAL NOTES

Fire Safety

A copy of the organiser's fire safety plan should be made available to QED staff on site